Global Energy Management System

Development and Deployment within ExxonMobil Chemical Company

Presented at the Texas Technology Showcase Energy-Efficient Process and Best Practices Chemical and Refining Processes

> Houston, Texas March 17, 2003

Matthew Knight ExxonMobil Chemical Company



Agenda

- Background & Case for Action
- ◆System Design
- ◆Deployment Strategy
- ◆Results and Conclusions
- ◆Example Project



Background & Case For Action Initiative's Objectives

- Enable ExxonMobil to become a recognized industry leader in energy utilization and efficiency
- ◆ Develop Global Energy Management System to improve and sustain energy efficiency at ExxonMobil refineries and chemical plants worldwide
- Provide common methodology for each site




Background & Case For Action

- Benchmarking against industry data
- Quantified significant Corporate opportunity
- Analyzed performance for refining and olefins plants at two levels:
 - ✓ Company-wide competitive analysis
 - ✓ Gaps of each individual ExxonMobil refinery and olefins plant relative to industry top performers


EXonMobil

Background & Case For Action Competitive Standing




- ExxonMobil participates in industry-wide competitive surveys
- Performance gaps versus top industry performers highlighted improvement opportunities

Background & Case For Action Gap Relative to Best Performing Plants





350 - 400 M \$/Year savings estimated if all ExxonMobil refineries and olefins plants could economically achieve leading-edge efficiency

System Design



System Design Methodology








Equipment Focus: Optimization of utilities, fired heaters, heat exchangers, and compressor trains

<u>Process Unit Focus:</u> Olefin Crackers, Fluid Catalytic Cracking Units, and Crude Distillation

System Design Products










- ◆ Best practices documented in 12 volume set of manuals
- Contain 1200 pages and identify over 200 key energy variables
- ◆ Cover key process, equipment, and utility operations
- Also address energy efficiency in project design



Deployment Strategy Address Largest Potential Opportunities First





Deployment Strategy **Rollout Process**

6 Months Preparation 6-8 Weeks Execution

0-8 Years *Implementation*

Preparation

Site Orientation **Select & Train Team Gather & Review Data Arrange Logistics**

Operations Assessments

Process Units Equipment Classes Utility Systems

Facilities Enhancements

Optimizations Modifications Additions

Transfer of Ownership

Deliverables

Gap Assessment Gap Closing Options Cost / Benefit Analysis Milestone Plan

Site **Ex**xonMobil G-EMS


Rollout Results

 Rollouts and Self-Assessments address 70-80% of total opportunity

◆ Potential savings equal to 15% of plant energy bill on average



Rollout Results





Conclusions

- ◆ A 15% reduction in site energy bills is potentially achievable through optimization of operations and economically attractive capital projects.
- Nearly half of the benefits can be achieved with little or no capital investment.
- Site Process Units is the largest opportunity for improvement
- Potential to reduce GHG emissions nearly 5 million tons per year at full implementation



Conclusions

- ◆ Achieving and maintaining energy benefits requires a lot of hard work during preparation, deployment, implementation and sustainment phases. Key requirements are:
 - ✓ Management approval of milestone plans and integration into overall improvement plans for the site.
 - ✓ Clear ownership of each line item.
 - ✓ Strong leadership from both local and regional management.
 - ✓ High quality technical support.
 - ✓ Continuous improvement through measurement, stewardship, networking and periodic reassessments.



Project Example

- An Olefins Plant Example of a G-EMS related Project is a Heat Integration System Modification
 - ✓ Project Identified During Initial G-EMS System Development
 - ✓ Heat Integration between Vaporizing NGL feed and Recovery Area
 Refrigeration System was found to be less than optimum.
 - ✓ Modifications to the system were Proposed During the Screening Phase for a Debottleneck Project.
 - ✓ Project was funded with the Debottleneck Project as an Energy Reduction Step.
 - ✓ Energy Reduction for the Refrigeration System was Calculated as ~16% even with associated through put increases.
 - ✓ System was Recently Started Up with Performance Within Design Parameters.

